




**KEY:**




**AREAS TO BE EXCAVATED**  
Form key for overlay/plane off existing surface,  
depth n.e. 40mm




**AREAS TO BE RE-CONSTRUCTED**  
SMA 10 Surf 40/60, depth 40mm  
AC 20 Dense Bin 100/150, depth 65mm  
Type 1 Stone Blinding Layer (where required)



**AREAS TO BE REGULATED**  
AC 10 Dense Bin 100/150, av. depth 40mm





Proposed PCC Kerbs



Overhanging Vegetation

Drawing 02 of 04





Gullies to be cleared and jetted upon completion of the works

Re-lay 5m of sunken pcc kerbs

Overlay carriageway surface with 40mm depth SMA


Remove existing road hump

Replace 3m of missing pcc kerbs

Replace 54m of pcc kerbs, raising level to ensure suitable kerb face

Cut back overhanging vegetation back to kerb edge

Plane off degraded surface and replace with regulating layer in preparation for overlay

 <div>Ribble Valley Borough Council Church Walk, Clitheroe. BB7 2RA Tel: (01200) 425111 <a href="http://www.ribblevalley.gov.uk">www.ribblevalley.gov.uk</a></div>		<b>Ribble Valley Borough Council</b> <b>Church Walk, Clitheroe. BB7 2RA</b> Tel: (01200) 425111 <a href="http://www.ribblevalley.gov.uk">www.ribblevalley.gov.uk</a>	
<b>PROJECT:</b>		Dewhurst Road, Langho	
<b>TITLE:</b>		Surfacing Improvements: Proposed Works (02 of 04)	
<b>STATUS:</b>		Tender	
<b>PROJECT REF:</b> ENG097		<b>DRAWING NUMBER:</b> E0805D / 2B	
<b>SCALE:</b> 1 : 200 @ A1	<b>DESIGNED:</b> N Y	<b>CHECKED:</b> A H	<b>DATE:</b> June 2022