PD Construction Consultants

7 Beech Street, Clitheroe, Lancs., BB7 2LL
Paul Derbyshire Dip.Surv. AssocRICS
tel: [redacted]

GENERAL SPECIFICATION OF WORKS - 30.09.26

NORTH STREET GARAGE, NORTH STREET, CLITHEROE

The proposed external repair / refurbishment works comprise of the following:

Removal of damaged and dilapidated corrugated profile fibre cement roof panels.

Removal of loose and damaged render to walls.

Removal of white u.p.v.c. window frames.

New roof panels to be Tata Steel Trisomet plastisol coated, inslated steel profiled panels - Goosewing Grey (RAL 7038).

New wall panels to be Tata Steel Trisomet plastisol coated, inslated steel profiled panels - Goosewing Grey (RAL 7038).

Edge trims to be plastisol coated steel – Anthraite Grey (RAL 7016).

Window frames to be u.p.v.c. – Anthraite Grey (RAL 7016).





[redacted]

Paul Derbyshire
Dip.Surv. AssocRICS.