



PLANT SCHEDULE

Trees	Ref	Species	Supply	Size(cm)	Girth(cm)
T1		Amelanchier 'Robin Hill'	450-600	14-18	14-18
T2		Prunus coccinea 'Chanticleer'	450-600	18-20	18-20

RS - Root Balled Stock
 Note: EHSd trees to be supplied with a clear stem of 2m in height.

All tree locations and species must be taken into consideration by the project Structural Engineer to ensure that foundation design accords with the specifications set out under Chapter 4.2 of the NHBC Standards. It is the Contractor's responsibility to ensure that all underground services have been located and identified in advance of tree pit excavation. No tree specification/specification will be amended without prior approval from the project Landscape Architect and/or the Client.

Specimen shrubs	Ref	Species	Supply	Size(cm)	Habit
S1		Photinia 'Rozan' Red Robin'	300-325	Std (112-14cm)	

All specimen shrubs to be planted in accordance with horticultural best practice guidelines. No feature shrub or climber species. Size or location should be altered without prior approval from the Landscape Architect. Planting beds to be mulched with 75mm layer of bark.

Hedgerows	Abbr	Species	Supply	Size(cm)	Habit	Ctrs(cm)
PRULU		Prunus lusitanica	10L	80-100	Bushy	40

All hedgerow shrubs to be planted in accordance with horticultural best practice guidelines. No hedgerow shrub species. Size or location should be altered without prior approval from the Landscape Architect. Planting beds to be mulched with 75mm layer of bark.

Shrubs	Abbr	Species	Supply	Size(cm)	Habit	Ctrs(cm)
AUCJA		Aucuba japonica	5L	40-60	Bushy	75
BRASU		Brachyglottis 'Sunshine'	10L	40-60	Bushy	70
CEATR		Ceratophyllum thyrsoiflorus repens	10L	40-60	Bushy	70
CHOAP		Choisya 'Aztica Pearl'	10L	40-60	Bushy	70
CHOTE		Choisya ternata	10L	40-60	Bushy	70
CHOTE		Choisya ternata 'Sundance'	10L	40-60	Bushy	70
CORALE		Cornus obovata 'Elegantissima'	10L	60-80	Branching	75
ELAFIMA		Eleagnus pungens 'Masculata'	10L	60-80	Bushy	75
EUFONGE		Euonymus fort. Emerald 'Gold'	10L	30-40	Bushy	60
EUFONGE		Euonymus fort. Emerald 'Gold'	10L	30-40	Bushy	60
EUFAMP		Euphorbia amygdalifolia 'Purpurea'	2L	-	Full pot	60
HEMAR		Hebe 'Majorie'	10L	40-60	Bushy	70
HEBW		Hebe 'Mr Winder'	10L	40-60	Bushy	70
HEBPQ		Hebe 'Purple Queen'	10L	40-60	Bushy	70
HEBUE		Hebe albertiana 'Red Edge'	10L	30-40	Bushy	65
HEBPS		Hebe pinguifolia 'Suffruticosa'	10L	40-60	Bushy	70
HEUMPP		Heuchera micrantha 'Palace Purple'	2L	-	Full pot	60
HYPHI		Hypocissus 'Hiddelet'	10L	40-60	Bushy	70
LAVANNU		Lavandula angustifolia 'Hiddelet'	10L	30-40	Bushy	60
LAVANNU		Lavandula angustifolia 'Munstead'	10L	30-40	Bushy	60
LONNIBG		Lonicera nitida 'Baggesen's Gold'	10L	40-60	Bushy	70
LONNIBG		Lonicera nitida 'Baggesen's Gold'	10L	40-60	Bushy	70
LONNIBG		Lonicera nitida 'Magdalen'	10L	40-60	Bushy	70
PHOFRR		Photinia 'Rozan' Red Robin'	5L	60-80	Bushy	75
PRULAC		Prunus laurocerasus 'Obovata'	10L	40-60	Bushy	70
ROSOFF		Rosmarinus officinalis	10L	40-60	Bushy	70
SKJARU		Sammia japonica 'Rubra'	10L	40-60	Bushy	70

All shrubs to be planted in accordance with horticultural best practice guidelines. No shrub species. Size or location should be altered without prior approval from the Landscape Architect. Individual species to be planted in groups of 3:7 within mixed species beds. Planting beds to be mulched with 75mm layer of bark.

- Turf to plot frontages to be Rolawn Medallion Turf or similar approved.
- Pre-seeded embankment mat to be installed to river embankment. Mat to be supplied by Greenflex (www.greenflex.co.uk) or similar product from an approved manufacturer.

- KEY**
- Site boundary
 - Existing trees and hedgerow to be retained
 - Existing trees and hedgerow to be removed
 - Proposed bench - to be Woodscape Type 2 Bench, height: 2m length, built-in. As supplied by Woodscape Ltd (www.woodscape.co.uk) or similar approved.

- NOTES**
- All landscape proposals must be referred to by the Structural Engineer during foundation design.
 - All planting has been indicated making every effort to avoid conflict with highway land. Prior to submission it is the client's responsibility to ensure that all landscaping is reviewed by the project manager/highway engineer to ensure there is no conflict with highway land and future adaptations.
 - Shrub beds topped to a depth of 300mm, turfed areas to a depth of 100mm.
 - All planting to be implemented in accordance with horticultural best practice guidelines.
 - No species, variety, size or position to be amended without the Landscape Architect's prior approval.
 - Before trees are planted, the Landscape Contractor shall ascertain the location of drains from the site manager, and shall if necessary make minor adjustments to tree positions to ensure that they are planted at least 1.5m from drains. They should however be planted no closer to houses/garages than is shown on the drawing, and if shown located in shrub beds, the shape of the latter should be adjusted if necessary to accommodate the revised tree position.
 - If planting conditions are particularly poor e.g. waterlogged/frozen ground or poor soils, the Site Manager must be notified. All works will halt until conditions are considered acceptable.
 - All planting must be mulched to a depth of 75mm and in accordance with horticultural best practice guidelines ensuring plants are not buried.
 - If planting is required outside the October-March season, bare root trees will be replaced by a containerised equivalent to be approved by the project landscape architect.